DESIGN ANALYSIS #1

Document Title: Lane Alignment at Southbound Off-Ramp Intersection Project Title: I-5, Northbound On-Ramp at Bakerview – Improvements

SR5 MP 257.65 TO MP 258.38

XL-5465 PIN-100591R

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION

Region: Northwest

Office: Bellingham

Prepared by: Albert Goo

Project Engineer: Melissa Ambler



Document Type: \square **Design Decision** / \boxtimes **Design Analysis (See Sec. 5 for Approvals)**

Document Phase: \square **Preliminary /** \boxtimes **Final**

Under 23 U.S. Code § 409 and 23 U.S. Code § 148, safety data, reports, surveys, schedules, lists compiled or collected for the purpose of identifying, evaluating, or planning the safety enhancement of potential crash sites, hazardous roadway conditions, or railway-highway crossings are not subject to discovery or admitted into evidence in a Federal or State court proceeding or considered for other purposes in any action for damages arising from any occurrence at a location mentioned or addressed in such reports, surveys, schedules, lists, or data.



Section 1: Background

Briefly describe the project:

This project constructs a new northbound on-ramp connection from Bakerview Road to I-5 and reconfigures Bakerview Road to optimize for future predicted growth and to accommodate the new on-ramp. See the Basis of Design (BOD) for Details.

Provide any background information important to understanding the decision(s):

Revisions to the channelization of Bakerview Road at the overpass has created the need for the intersection of W. Bakerview Road, W. Maplewood Ave and the existing northbound on-ramp / southbound off-ramp to be reconstructed. The wide existing through lane on the southbound off-ramp was split into two separate lanes in order to accommodate an additional turning movement onto eastbound Bakerview Road.

It should be noted that the 2040 anticipated increase in vehicles travelling from the southbound off-ramp onto eastbound Bakerview road is significantly greater than the volume of traffic traveling in a straight through movement onto Maplewood Avenue.

Related documents (such as a Basis of Design):

- Interstate 5 / Bakerview Road, Exit 258 Interchange Justification Report (IJR) Approved June 27, 2017
- Basis of Design PIN 100591R / I-5, Northbound On-Ramp at Bakerview Improvements Approved June 1, 2018



Section 2: Decision Description

Describe the decision(s) that will be discussed. Identify the design elements that are involved, including the locations. Identify the proposed dimensions and how they compare to Design Manual Guidance.

ID#	Design Element	Location	Guidance	Proposed	Shown on (Sheet #)
IA1	Intersection Angle	A Line	6' Max, 11:1 min	6.8', 20:1 taper rate	DM 1310.02(3)
			taper rate		

Details

(M1) Design Manual (July 2017) section 1310.02(3), allows for a lane offset of up to 6' at an intersection, and DM Exhibit 1310-1 requires a minimum taper rate of at least 11:1 on roadways with a 25 mph speed limit. Because the existing through lane was 22' wide, the lane was split into a right-turn/through lane and a dedicated left turn lane. This lane split offset the through lane from the center of the receiving lane.

If guidance other than the Design Manual was used describe it here

N/A

Section 3: Options Evaluation and Decision

Discuss the evaluation <u>methodology</u>. Describe the metrics/considerations that will be used to choose between options. Describe methodology (quantitative or qualitative) and any performance targets. The performance metrics, methods and targets you choose will be part of your performance trade-offs "story"

In order to accommodate anticipated 2040 traffic load, vehicle storage capacity of the turning and through lanes of the SB off-ramp were given a priority. Safety, the cost of rebuilding an intersection, and compatibility with the IJR were also considered in the comparison



	*	Metrics / Considerations				
Options Comparison Table	Associated Issues (identified in Section 2)	Storage Capacity	Safety Performance	Operational and Mobility Performance	CN3 – Cost effectiveness / scalability	CN5 – Compatibility with the IJR
Option 1: Two left turn lane option with offset through lane	IA1	+	0	+	+	+
Option 2: Two left turn lane option with rebuilt intersection	IA1	+	0	+		+
Option 3: One lane option with left turn integrated into existing through (no build)	IA1	-	0		+	-

Detailed Description of the options evaluated as follows:

Option 1 – Separating the existing southbound through lane into a left-turn lane onto eastbound Bakerview Road and a through/right turn lane. This option does not change roadway geometry, only channelization, and splits an existing lane into two lanes.

Option 2 – Rebuilding the intersection to accommodate a new turn lane and to better align a new southbound through lane into Maplewood Avenue. This option changes roadway geometry and channelization, and builds out a new turn lane and re-orients Maplewood.

Option 3 – Re-channelizing the existing southbound through lane into a single hybrid left/right/through lane. This option does not change roadway geometry, only channelization. This option does not add any additional lanes for storage.

Discuss the <u>performance tradeoffs</u> shown in the table, and compare the performance of the options:

From the options comparison table above, the introduction of a dedicated left-turn lane improves the storage capacity of the southbound off-ramp and the intersection's operational mobility. The anticipated increase of southbound traffic turning onto eastbound Bakerview in 2040 emphasizes the importance of improving this turning movement and the storage capacity of the ramp.

Conversely, option 2 and option 3 both keep the through/right lane of the off-ramp aligned with Maplewood Avenue, providing a clear path. Option 1's skew (6.8' instead of the 6.0' standard) means that vehicles making a through movement will need to slightly realign their vehicle to match into Maplewood.



Discuss any mitigating measures added to address performance trade-offs:

It should be noted that the maximum offset of Option 1 is only 0.8' above the maximum of 6.0' listed in the design manual, and is at almost half the taper rate for the posted speed. This, coupled with the offset being spread out over 5 perpendicular lanes of traffic, makes the scenario presented in Option 1 a more gradual skew than what is accepted in the design manual. Discussion with NWR Traffic have revealed that the safety difference between option 1 and option 2 are negligible. A similar situation exists nearby at the SR 542 and NB Off-Ramp intersection and has had no issues.

Option 1 and Option 2 both create dedicated left turn-lanes on the off-ramp making them operationally identical, but the differential in cost between the two options is significant. Reorienting Maplewood Ave to match in the newly aligned through lane would require moving the road and all electrical components associated with the intersection as well as additional environmental mitigation, as much of the area adjacent to the Maplewood is heavily wooded. In exchange, option 2's realignment of the receiving road would allow users to drive straight off the off-ramp instead of at a slight skew.

Option 3 converts the existing through/right turn lane of SB I-5 into an left/right/through hybrid lane. This does not increase storage capacity or improve the operational capacity of the intersection, but it does allow vehicles to travel directly into Maplewood Avenue without any skew.

Preferred Option and reasoning for selecting the preferred option:

Option 1, which splits the existing wide through lane into a right/through and a dedicated left turn lane, allows for an increase in storage capacity and improvements to mobility at a significantly reduced cost. While the implementation of a skewed receiving lane is sub-optimal, the distance of the skew is marginally higher than what is accepted in the DM, and the length of the intersection reduces the taper rate to a significantly better than what the DM allows. Option 1 helps resolve the issues of the anticipated 2040 traffic loading and thus fully complies with the IJR.

Evaluation Sheet #_

Attach additional evaluations (section 3) as needed to address additional areas

Section 4: Attachments					
⊠ Vicinity Map					
☐ Others (list below)					



Section 5: Approvals

Design Decisions approved by Project Engineer. See WSDOT Design Manual Chapter 300 and required approvals for Design Analysis

Design Analysis Approvals:

■ WSDOT Region / ■ WSDOT HQ / ■ FHWA

Design Decision Approval / Design Analysis Recommended for Approval:

Signed Melius Ambler

Print Melissa Ambler

Oct 8, 2020

Project Engineer

Design Analysis Approval:

Signed Chris Damitio (Oct 8, 2020 12:25 PDT)

Print Chris Damitio

Date Oct 8, 2020

WSDOT Region

Design Analysis Approval:

Signed Sem/C/Noon

Print Dean R. Moon

Date Oct 8, 2020

WSDOT HQ

Design Analysis Approval:


Signed Angelo Rivera (Oct 15, 2020 09:39 PDT)

Print Angel D Rivera

Date Oct 15, 2020

FHWA







Design Analysis # 1 Lane Alignment at Southbound Off-Ramp Intersection

Final Audit Report 2020-10-15

Created: 2020-10-08

By: Samantha McDougle (mcdougs@wsdot.wa.gov)

Status: Signed

Transaction ID: CBJCHBCAABAA3dHUInj81OZHrtvzHnSAhJ2klfPYqNyA

"Design Analysis # 1 Lane Alignment at Southbound Off-Ramp I ntersection" History

- Document created by Samantha McDougle (mcdougs@wsdot.wa.gov) 2020-10-08 6:47:37 PM GMT- IP address: 198.238.213.156
- Document emailed to Melissa Ambler (AmblerM@wsdot.wa.gov) for signature 2020-10-08 6:51:34 PM GMT
- Email viewed by Melissa Ambler (AmblerM@wsdot.wa.gov) 2020-10-08 7:12:33 PM GMT- IP address: 198.238.213.147
- Document e-signed by Melissa Ambler (AmblerM@wsdot.wa.gov)

 Signature Date: 2020-10-08 7:13:15 PM GMT Time Source: server- IP address: 198.238.213.147
- Document emailed to Chris Damitio (DamitiC@wsdot.wa.gov) for approval 2020-10-08 7:13:16 PM GMT
- Email viewed by Chris Damitio (DamitiC@wsdot.wa.gov) 2020-10-08 7:25:20 PM GMT- IP address: 198.238.213.151
- Document approved by Chris Damitio (DamitiC@wsdot.wa.gov)

 Approval Date: 2020-10-08 7:25:34 PM GMT Time Source: server- IP address: 198.238.213.151
- Document emailed to Dean R. Moon (moondr@wsdot.wa.gov) for approval 2020-10-08 7:25:36 PM GMT
- Email viewed by Dean R. Moon (moondr@wsdot.wa.gov) 2020-10-08 7:54:40 PM GMT- IP address: 198.238.213.155
- Document approved by Dean R. Moon (moondr@wsdot.wa.gov)

 Approval Date: 2020-10-08 7:59:42 PM GMT Time Source: server- IP address: 198.238.213.155



Document emailed to Angel D Rivera (angel.d.rivera@dot.gov) for approval 2020-10-08 - 7:59:44 PM GMT

Email viewed by Angel D Rivera (angel.d.rivera@dot.gov) 2020-10-15 - 4:36:11 PM GMT- IP address: 23.103.200.254

Document approved by Angel D Rivera (angel.d.rivera@dot.gov)

Approval Date: 2020-10-15 - 4:39:13 PM GMT - Time Source: server- IP address: 152.119.228.235- Signature captured from device with phone number XXXXXXX7396

Agreement completed. 2020-10-15 - 4:39:13 PM GMT